



CITY OF BEVERLY HILLS
DEPARTMENT OF PUBLIC WORKS
345 N. FOOTHILL ROAD
BEVERLY HILLS, CALIFORNIA 90210

ADDENDUM NO. 1

409 WALKER DRIVE

FOUNDATION UPGRADE AND PERIMETER FENCE REPLACEMENT PROJECT

BID NO. 17-63

DATE OF ADDENDUM: JANUARY 5, 2018

The following changes, omissions, and/or additions to the Specifications and/or Drawings shall apply to proposals made for and to the execution of the various parts of the work affected thereby, and all other conditions shall remain the same.

In case of conflict between Drawings, Specifications, and this Addendum, this Addendum shall govern.

ITEM NO. 1 – ADD ALTERNATIVE No. 3

The following add alternative shall be included in the bid.

Alternative No. 3:

Refer to sheet # T-1, south fence Key notes #1 & 2, indicated detail 2/S-2.1 with a retaining wall shall be an add alternate item, base bid shall include standard pole footing (8/S-1.2) , post and chain link fencing similar to existing without the retaining wall.

The Bid Form has been revised (attached) to include this Alternative item.

ITEM NO. 2 –

Refer to Sheet# T-1 LEGEND, indicated Galvanized chain link fence shall be heavy gauge and woven, the shall be galvanized in base bid and Vinyl coated in Alternate No. 1 as indicated.

ITEM NO. 3

Refer to Sheet # T-1, Keynote #1, provide 3" perforated PVC drain pipe behind retaining wall running east-west in lieu of indicated weep holes at 6' o.c., pipe to day light on east and west down slopes. Also, add 60 mil. Liquid membrane waterproofing on the entire length of the retaining wall.

END OF ADDENDUM